

# Restoration & Future Management of the River Ems

Based on projects delivered by: the Arun & Rother Rivers Trust (ARRT) and Wild Trout Trust (WTT) 2015/16+

> RRC Conference April'17 Ses Wright ARRT Project Officer

## **River Ems: Location and Geological Context**



### **Rationale for Multiple Restoration Projects**

• River Ems WFD Ecological Status (2009-15): Poor



→ Failing for Fish, Dynamics of Flow (heavily modified)
→ Due to: Resource Pressures & Obstructions

 Research by the EA & Portsmouth Water on the impact of abstraction support the need for river augmentation on the Ems

 Improved augmented flow to offset abstraction pressures combined with channel modifications and fish easements open up opportunities to restore a high quality chalk stream capable of supporting a healthy and diverse ecology







**Project Planning** 

#### **Objectives to Set & Queries to Resolve:-**

**Objectives**:

- Restore Bed Variation: increase diversity of channel morphology
- Restore Channel Sinuosity: to add dynamics of flow and natural scour processes
- Create a Low-flow Channel: to help sustain river ecology during dry periods

#### **Pre-works Site Conditions:**

- → No defined bankside (cattle poaching & historic watercress works)
- → Uniform straightened channel: how many bends and curves to design?
- ightarrow No pools or riffles; shallow depth with sluggish flow velocity throughout

#### **Queries and questions to Answer:**

- → Monitor/note changing wet-channel widths over winter and summer months
- $\rightarrow$  Estimate typical change in water depth over winter and summer seasons
- $\rightarrow$  Estimate number of pools and riffles to be created over ~300m
- $\rightarrow$  Determine width of low-flow channel and check gradient
- → Estimate depth (and length) of required pools
- → Estimate quantity of sedge/rush required for new bankside low-rise berms





## **Deepsprings Restoration Aims**



### Resources required for restoration works

2 Excavators & 1 Dumper to break into firm flint bed for construction of pools, low-rise berms and scrape creation (2 main contractors + supervisor & planner)
Natural flint gravels and bed substrate (largely compacted flint gravels, chalk, clays and pebbles) to construct low-rise shoulder berms

 Suitable good-rooting semi-aquatic plants to top dress over the flint berms compacted down by machines





## Improved Plan Form Sinuosity, Greater Bed Level Variation & 2 Stage Channel



# Deepsprings: Before & After





An over-wide, shallow and uniform channel is restored with greater planform sinuosity and bed level variation with a 'two stage' channel to take a wider range of flows. Stock fencing delivered to stop cattle poaching and ingress of topsoil/bovine waste into the channel. Improved compensation flow site located upstream of restoration works. Initial observed improvements: clear self-cleaning gravel reaches, flowering Water Crowfoot and increased Flora & Fauna biodiversity, Improved flow dynamics, young brown trout spotted at Watersmeet (2016), less sediment, future need for some in-channel maintenance with limited tree planting to create dapped shade







Thank you for listening to my presentation

I am happy to answer any questions you may have!

Many thanks to Portsmouth Water for funding the Deepsprings works, for the WTT who helped to deliver the works with ARRT, to the Catchment Partnership Action Fund and the Environment Agency (WFD) for the additional Ems improvement projects and to the numerous organisations and individuals who supported this project especially Portsmouth Water, the Environment Agency, Natural England and Sussex Wildlife Trust